



LEED Certification Review Report

This report contains the results of the technical review of an application for LEED® certification submitted for the specified project. LEED certification is an official recognition that a project complies with the requirements prescribed within the LEED rating systems as created and maintained by the U.S. Green Building Council® (USGBC®). The LEED certification program is administered by Green Business Certification Inc. (GBCI®).

1-7 Dalton

Project ID 1000042996
Rating system & version LEED-NC
Project registration date 06/03/2014



Silver Certified

CERTIFIED: 40-49, SILVER: 50-59, GOLD: 60-79,
PLATINUM: 80+



LEED 2009 NEW CONSTRUCTION

ATTEMPTED: 54, DENIED: 0, PENDING: 0, AWARDED: 54 OF 110 POINTS



SUSTAINABLE SITES 17 OF 26

SSp1 Construction Activity Pollution Prevention	Y
SSc1 Site Selection	1 / 1
SSc2 Development Density and Community Connectivity	5 / 5
SSc3 Brownfield Redevelopment	0 / 1
SSc4.1Alternative Transportation-Public Transportation Access	6 / 6
SSc4.2Alternative Transportation-Bicycle Storage and Changing Rooms	1 / 1
SSc4.3Alternative Transportation-Low-Emitting and Fuel-Efficient Vehicles	0 / 3
SSc4.4Alternative Transportation-Parking Capacity	2 / 2
SSc5.1Site Development-Protect or Restore Habitat	0 / 1
SSc5.2Site Development-Maximize Open Space	1 / 1
SSc6.1Stormwater Design-Quantity Control	0 / 1
SSc6.2Stormwater Design-Quality Control	0 / 1
SSc7.1Heat Island Effect, Non-Roof	0 / 1
SSc7.2Heat Island Effect-Roof	1 / 1
SSc8 Light Pollution Reduction	0 / 1



WATER EFFICIENCY 4 OF 10

WEp1 Water Use Reduction-20% Reduction	Y
WEc1 Water Efficient Landscaping	2 / 4
WEc2 Innovative Wastewater Technologies	0 / 2
WEc3 Water Use Reduction	2 / 4



ENERGY AND ATMOSPHERE 12 OF 35

EAp1 Fundamental Commissioning of the Building Energy Systems	Y
EAp2 Minimum Energy Performance	Y
EAp3 Fundamental Refrigerant Mgmt	Y
EAc1 Optimize Energy Performance	7 / 19
EAc2 On-Site Renewable Energy	0 / 7
EAc3 Enhanced Commissioning	2 / 2
EAc4 Enhanced Refrigerant Mgmt	2 / 2
EAc5 Measurement and Verification	1 / 3
EAc6 Green Power	0 / 2



MATERIALS AND RESOURCES 6 OF 14

MRp1 Storage and Collection of Recyclables	Y
MRC1.1Building Reuse-Maintain Existing Walls, Floors and Roof	0 / 3
MRC1.2Building Reuse - Maintain 50% of Interior Non-Structural Elements	0 / 1
MRC2 Construction Waste Mgmt	2 / 2
MRC3 Materials Reuse	0 / 2
MRC4 Recycled Content	2 / 2
MRC5 Regional Materials	2 / 2
MRC6 Rapidly Renewable Materials	0 / 1
MRC7 Certified Wood	0 / 1



INDOOR ENVIRONMENTAL QUALITY 8 OF 15

IEQp1 Minimum IAQ Performance	Y
IEQp2 Environmental Tobacco Smoke (ETS) Control	Y
IEQc1 Outdoor Air Delivery Monitoring	1 / 1
IEQc2 Increased Ventilation	0 / 1
IEQc3.1Construction IAQ Mgmt Plan-During Construction	1 / 1
IEQc3.2Construction IAQ Mgmt Plan-Before Occupancy	0 / 1
IEQc4.1Low-Emitting Materials-Adhesives and Sealants	1 / 1
IEQc4.2Low-Emitting Materials-Paints and Coatings	1 / 1
IEQc4.3Low-Emitting Materials-Flooring Systems	1 / 1
IEQc4.4Low-Emitting Materials-Composite Wood and Agrifiber Products	0 / 1
IEQc5 Indoor Chemical and Pollutant Source Control	0 / 1
IEQc6.1Controllability of Systems-Lighting	1 / 1
IEQc6.2Controllability of Systems-Thermal Comfort	0 / 1
IEQc7.1Thermal Comfort-Design	1 / 1
IEQc7.2Thermal Comfort-Verification	0 / 1
IEQc8.1Daylight and Views-Daylight	0 / 1
IEQc8.2Daylight and Views-Views	1 / 1



INNOVATION IN DESIGN 6 OF 6

IDc1.1 Innovation in Design - Public Transportation	1 / 1
IDc1.1 Innovation in Design	0 / 1
IDc1.2 Innovation in Design- SSC5.2 40% Open Space	1 / 1
IDc1.2 Innovation in Design	0 / 1
IDc1.3 Innovation in Design-MRp2 Solid Waste Mgmt Policy	1 / 1
IDc1.3 Innovation in Design	0 / 1
IDc1.4 Innovation in Design	0 / 1
IDc1.4 Innovation in Design - Green Education	1 / 1
IDc1.5 Innovation in Design	0 / 1
IDc1.5 Innovation in Design - MRC5 Regional Material Exemplary Performance	1 / 1
IDc2 LEED® Accredited Professional	1 / 1



REGIONAL PRIORITY CREDITS 1 OF 4

SSc7.2Heat Island Effect-Roof	1 / 1
-------------------------------	-------

TOTAL

54 OF 110

CREDIT DETAILS



Project Information Forms

PIf1 : Minimum Program Requirements

Approved

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project complies with all Minimum Program Requirements. The project will comply with MPR 6: Must Commit to Sharing Whole-Building Energy and Water Usage Data via Option 1: Third Party Data Source. The project is located in Boston, MA.

PIf2 : Project Summary Details

Approved

DESIGN PRELIMINARY REVIEW

The LEED Form includes the required project summary details. There is one building in this LEED application with a total of 62 stories and 856,359 gross square feet.

PIf3 : Occupant and Usage Data

Approved

DESIGN PRELIMINARY REVIEW

The LEED Form includes the required occupant and usage data. The project consists primarily of Multi-Family Residential: Condominium spaces. The average user value is 584, the peak user value is 497, and the FTE value is 200. The project includes 805 residents.

PIf4 : Schedule and Overview Documents

Approved

DESIGN PRELIMINARY REVIEW

The LEED Form includes the design and construction schedule. The date of substantial completion is December 16, 2019 and the date of occupancy is February 07, 2020. The required documents have been uploaded.



Sustainable Sites

SSp1 : Construction Activity Pollution Prevention

Awarded

CONSTRUCTION FINAL REVIEW

The additional documentation demonstrates compliance.

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form has been provided. However, to demonstrate compliance, the following must be addressed.

TECHNICAL ADVICE

1. The LEED Form is not complete. Provide a completed form.
2. It is unclear if the ESC plan includes the proper measures for the prevention of air pollution (dust and particulate matter). Provide a revised ESC plan and supporting documentation that includes detailed information describing the measures taken for the prevention of polluting the air with dust and particulate matter.

SSc1 : Site Selection

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project site does not meet any of the prohibited criteria.

SSc2 : Development Density and Community Connectivity

POSSIBLE POINTS: 5

ATTEMPTED: 5, DENIED: 0, PENDING: 0, AWARDED: 5

Awarded : 5

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project complies with Option 2: Community Connectivity.

SSc3 : Brownfield Redevelopment

POSSIBLE POINTS: 1

Not Attempted

SSc4.1 : Alternative Transportation-Public Transportation Access

POSSIBLE POINTS: 6

ATTEMPTED: 6, DENIED: 0, PENDING: 0, AWARDED: 6

Awarded : 6

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project complies with Option 1: Rail Station, Bus Rapid Transit, and Ferry Terminal Proximity and is located within a one-half mile walking distance of a qualifying transit system.

SSc4.2 : Alternative Transportation-Bicycle Storage and Changing Rooms

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project complies with Case 1: Commercial or Institutional Projects and that the residential portions of the project comply with Case 2: Residential Projects. Bicycle storage facilities (35) have been provided to serve 7.04% of the LEED project FTE and transient occupants, measured at peak occupancy, and shower facilities (2) have been provided for 1% of the LEED project FTE occupants. In addition, Covered bicycle storage facilities (174) have been provided to serve 21.61% of the LEED project residents. It is noted that LI 2422, 1567, 1766, and 1698 address the exclusion of hotel guests from the bicycle storage facilities requirement.

SSc4.3 : Alternative Transportation-Low-Emitting and Fuel-Efficient Vehicles

POSSIBLE POINTS: 3

Not Attempted

SSc4.4 : Alternative Transportation-Parking Capacity

POSSIBLE POINTS: 2

ATTEMPTED: 2, DENIED: 0, PENDING: 0, AWARDED: 2

Awarded : 2**DESIGN PRELIMINARY REVIEW**

The LEED Form states that no new parking has been created within the LEED project scope of work.

SSc5.1 : Site Development-Protect or Restore Habitat

POSSIBLE POINTS: 1

Not Attempted

SSc5.2 : Site Development-Maximize Open Space

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1**DESIGN PRELIMINARY REVIEW**

The LEED Form states that the project complies with Case 3: Sites with Zoning Ordinances but No Open Space Requirements. The open space provided is equal to 42.1% of the total site area.

SSc6.1 : Stormwater Design-Quantity Control

POSSIBLE POINTS: 1

Withdrawn

SSc6.2 : Stormwater Design-Quality Control

POSSIBLE POINTS: 1

Withdrawn

SSc7.1 : Heat Island Effect, Non-Roof

POSSIBLE POINTS: 1

Withdrawn

SSc7.2 : Heat Island Effect-Roof

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1**DESIGN PRELIMINARY REVIEW**

The LEED Form states that the project complies with Option 1 and 105.37% of the building roof surface has a Solar Reflectance Index meeting the credit requirements.

SSc8 : Light Pollution Reduction

POSSIBLE POINTS: 1

Not Attempted



Water Efficiency

WEp1 : Water Use Reduction-20% Reduction

Awarded

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project has reduced potable water use by 32.85%. It is note that the Restaurant Customers lavatory has been indicated as belonging to the Private Lavatory Faucet fixture family, yet it does not appear that the private lavatory classification is appropriate for this project type. Private or private use applies to plumbing fixtures in residences, apartments, and dormitories; private (non-public) bathrooms in transient lodging facilities (hotels and motels); and private bathrooms within hospitals and nursing facilities. All other facilities are considered to be public or public use. When this issue is addressed and the form is recalculated, the project has reduced potable water use by 32.79%.

WEc1 : Water Efficient Landscaping

Awarded : 2

POSSIBLE POINTS: 4

ATTEMPTED: 2, DENIED: 0, PENDING: 0, AWARDED: 2

DESIGN APPEAL REVIEW

The additional documentation provided demonstrates compliance for a 51% reduction in potable water consumption for irrigation and for a 51% reduction in total water used for irrigation.

DESIGN FINAL REVIEW

The additional documentation provided states that the landscaping and irrigation systems have been designed to reduce potable water consumption for irrigation by 51% and reduce the total water used for irrigation by 51%. However, the Baseline Area of the Landscape Types have been significantly changed from the Design Preliminary Review (Turf 2,042 SF, Tree 1,390 SF, and Mixed - Trees/Groundcover 720 SF) to the Final Review (Turf 2,906 SF, Tree 623 SF, and Mixed - Trees/Groundcover 623 SF) without explanation. The additional documentation does not demonstrate compliance.

DESIGN PRELIMINARY REVIEW

The LEED Form states that the landscaping and irrigation systems have been designed to reduce potable water consumption for irrigation by 51.65% and reduce the total water used for irrigation by 51.65%. However, to demonstrate compliance, the following must be addressed.

TECHNICAL ADVICE

1. Provide revised calculations to ensure that the baseline case uses (turf grass) average values for species factor (ks). For additional information, refer to the calculations section within WEc1 in the LEED BD+C v2009 Reference Guide.

WEc2 : Innovative Wastewater Technologies

Not Attempted

POSSIBLE POINTS: 2

WEc3 : Water Use Reduction

Awarded : 2

POSSIBLE POINTS: 4

ATTEMPTED: 2, DENIED: 0, PENDING: 0, AWARDED: 2

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project has reduced potable water use by 33%.



Energy And Atmosphere

EAp1 : Fundamental Commissioning of the Building Energy Systems

Awarded

CONSTRUCTION FINAL REVIEW

The additional documentation demonstrates compliance.

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that fundamental commissioning is complete. However, to demonstrate compliance, the following must be addressed.

TECHNICAL ADVICE

1. Pf4 Schedule and Overview Documents indicates that substantial completion occurred on Dec 16, 2019; therefore, it is anticipated that the executive summary is complete. Provide a copy of the executive summary of the commissioning report ensuring that a list of the systems commissioned, a summary of issues corrected, and a list of any major outstanding/unresolved issues is included.

EAp2 : Minimum Energy Performance

Awarded

DESIGN FINAL REVIEW

The LEED Form has been revised to address the issues outlined in the Preliminary Review and states that the project has achieved an energy cost savings of 14.9%. The total predicted annual energy consumption for the project is 8,494,192 kWh/year of electricity and 212,500 therms/year of natural gas.

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project complies with Option 1: Whole Building Energy Simulation and has achieved an energy cost savings of 15.1%. However, to demonstrate compliance, the following comments requiring a project response must be addressed for the Final Review.

TECHNICAL ADVICE

REVIEW COMMENTS REQUIRING A PROJECT RESPONSE

1. Provide the following:

a. A narrative response to each Preliminary Review comment below.

b. A narrative describing any additional changes made to the energy models between the Preliminary and Final Review phases not addressed by the responses to the review comments. The mandatory comments are perceived to reduce the projected savings for the Proposed design. If the projected savings increase substantially in the Final submission, without implementing any optional comments that may improve performance, a narrative explanation for these results must be provided.

2. The Minimum Energy Performance Calculation (MEPC) indicates that the Vertical Glazing Area for the Baseline case is 35.2%. ASHRAE 90.1-2010 Table G3.1 section 5 requires vertical fenestration areas for new buildings and additions shall equal that in the Proposed design or 40% of gross above grade wall area, whichever is smaller, and shall be distributed on each face of the building in the same proportions in the Proposed design. Revise the Baseline case to reflect 40% vertical glazing area.

3. From the information provided, it is unclear if automatic lighting controls other than those listed in the MEPC are included in the project and in the Proposed Case energy model. A demand savings of 8.6% is claimed in the Performance Outputs compared to consumption savings of 13.4%, indicating that the Baseline and Proposed case lighting are on differing schedules. If additional lighting controls are included, provide a narrative describing the controls and how they are implemented in the Proposed energy model. Describe how the controls conform to Table G3.1 Paragraph 6(f). Revise the energy models, update Supplemental Table 1.4, and revise the supporting documentation if necessary.

4. It appears that each Baseline pump has been modeled with a power of approximately 22 W/gpm. ASHRAE Interpretation ASHRAE/IES IC 90.1-2007-14 indicates that the Baseline pump power of 22 W/gpm from Section G3.1.3.10 is inclusive of all Baseline chilled water pumps. This ruling is confirmed by LEED Interpretation 10299. The Baseline pump power shall be evenly distributed between the Baseline primary and secondary chilled water pumps. Alternatively, if the Proposed case has primary/secondary chilled water pumps, the Baseline pump power may be distributed between the Baseline primary and secondary pumps consistent with the Proposed design. Update the model and Supplemental Table 1.4 to be in compliance with these ASHRAE and LEED Interpretations.

EAp3 : Fundamental Refrigerant Management

Awarded

DESIGN PRELIMINARY REVIEW

The LEED Form states that there are no CFC-based refrigerants serving the project building.

EAc1 : Optimize Energy Performance

POSSIBLE POINTS: 19

ATTEMPTED: 7, DENIED: 0, PENDING: 0, AWARDED: 7

Awarded : 7

DESIGN FINAL REVIEW

Additional documentation has been provided for EAp2: Minimum Energy Performance claiming an energy cost savings of 14.9%.

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project has achieved an energy cost savings of 15.1%. However, to demonstrate compliance, the following must be addressed.

TECHNICAL ADVICE

1. Refer to the comments within EAp2: Minimum Energy Performance and resubmit this credit.

EAc2 : On-Site Renewable Energy

POSSIBLE POINTS: 7

Not Attempted

EAc3 : Enhanced Commissioning

POSSIBLE POINTS: 2

ATTEMPTED: 2, DENIED: 0, PENDING: 0, AWARDED: 2

Awarded : 2

CONSTRUCTION FINAL REVIEW

The additional documentation demonstrates compliance.

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that enhanced commissioning has been implemented. However, to demonstrate compliance, the following must be addressed.

TECHNICAL ADVICE

1. Refer to the comments within EAp1: Fundamental Commissioning of Building Energy Systems and resubmit this credit.
2. The provided systems manual does not contain sufficient detail to confirm that it provides future operating staff with the information needed to understand and optimally operate the commissioned systems. Update the manual to include detail on at least two sections recommended by the LEED BD+C v2009 Reference Guide; final version of the basis of design; system single-line diagrams; as-built sequences of operations, control drawings, and original setpoints; operating instructions for integrated building systems; recommended schedule of maintenance requirements and frequency; recommended schedule for retesting of commissioned systems with blank test forms from the original commissioning plan; recommended schedule for calibrating sensors and actuators; other sections which provide future operating staff with information needed to understand and optimally operate the commissioned systems. If the systems manual is in draft form, it must still contain sufficient detail from at least two of the sections listed above.
3. A scope of work proposal has been provided in lieu of an executed contract. Provide the contract between the Owner and the Commissioning Agent which ensures post-construction commissioning activities.

EAc4 : Enhanced Refrigerant Management

POSSIBLE POINTS: 2

ATTEMPTED: 2, DENIED: 0, PENDING: 0, AWARDED: 2

Awarded : 2

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project selected refrigerants and HVACR systems that minimize or eliminate the emission of compounds that contribute to ozone depletion and global climate change. Additionally, all fire suppression systems in the LEED project do not use ozone-depleting substances including CFCs, HCFCs, or halons. The refrigerant impact calculation indicates that the total refrigerant impact of the LEED project is 74 per ton, which is less than the maximum allowable value of 100.

EAc5 : Measurement and Verification

POSSIBLE POINTS: 3

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that the project complies with Option 3 and has committed to sharing whole-building energy and water data through an approved third-party data source.

EAc6 : Green Power
POSSIBLE POINTS: 2

Not Attempted

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that the project has a two-year purchase agreement to procure 35% of electricity for this LEED project that meets the Green-e definition for renewable power using Option 1: Whole Building Energy Simulation. However, to demonstrate compliance, the following must be addressed.

TECHNICAL ADVICE

1. A price proposal has been provided in lieu of the contract. Provide the contract to purchase renewable power and ensure that the documentation includes the name of the provider, the total annual electricity provided, and the term of the contract.



Materials And Resources

MRp1 : Storage and Collection of Recyclables

Awarded

DESIGN FINAL REVIEW

The additional documentation demonstrates compliance.

MRc1.1 : Building Reuse-Maintain Existing Walls, Floors and Roof

POSSIBLE POINTS: 3

Not Attempted

MRc1.2 : Building Reuse - Maintain 50% of Interior Non-Structural Elements

POSSIBLE POINTS: 1

Not Attempted

MRc2 : Construction Waste Management

POSSIBLE POINTS: 2

ATTEMPTED: 2, DENIED: 0, PENDING: 0, AWARDED: 2

Awarded : 2

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that the project has diverted 80% of the on-site generated construction waste from landfill.

MRc3 : Materials Reuse

POSSIBLE POINTS: 2

Not Attempted

MRc4 : Recycled Content

POSSIBLE POINTS: 2

ATTEMPTED: 2, DENIED: 0, PENDING: 0, AWARDED: 2

Awarded : 2

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that 22.39% of the total building materials content, by value, has been manufactured using recycled materials.

Items that do not require a response for this project, but should be considered for future projects:

1. The provided manufacturer's documentation indicates that the recycled content reported for Sadev Biloba Hinges is based on an industry average, whereas the calculations for this credit require actual, product-specific recycled content values. If the recycled content is unknown for steel products, then the LEED default recycled content value (25% post-consumer) must be used.

MRc5 : Regional Materials

POSSIBLE POINTS: 2

ATTEMPTED: 2, DENIED: 0, PENDING: 0, AWARDED: 2

Awarded : 2

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that 63.42% of the total building materials value includes materials and products that have been manufactured and extracted within 500 miles of the project site.

MRc6 : Rapidly Renewable Materials

POSSIBLE POINTS: 1

Not Attempted

MRc7 : Certified Wood

POSSIBLE POINTS: 1

Withdrawn



Indoor Environmental Quality

IEQp1 : Minimum Indoor Air Quality Performance

Awarded

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project is mechanically ventilated and that the ventilation system has met the minimum requirements of ASHRAE 62.1-2007.

IEQp2 : Environmental Tobacco Smoke (ETS) Control

Awarded

CONSTRUCTION PRELIMINARY REVIEW

The additional documentation demonstrates compliance.

DESIGN PRELIMINARY REVIEW

The LEED Form states that smoking is prohibited within the building, except in designated smoking areas. However, as differential pressure test reports are required to document compliance, this prerequisite cannot be reviewed until the tests are completed after the end of construction phase. This prerequisite has been marked as pending. Resubmit this prerequisite when submitting for the Construction Preliminary Review.

IEQc1 : Outdoor Air Delivery Monitoring

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1

DESIGN FINAL REVIEW

The additional documentation demonstrates compliance.

IEQc2 : Increased Ventilation

POSSIBLE POINTS: 1

Not Attempted

IEQc3.1 : Construction IAQ Management Plan-During Construction

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1

CONSTRUCTION FINAL REVIEW

The additional documentation demonstrates compliance.

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that the project reduces air quality problems resulting from construction to promote the comfort and well-being of construction workers and building occupants. However, to demonstrate compliance, the following must be addressed.

TECHNICAL ADVICE

1. The LEED Form is not complete. Provide a completed form.

IEQc3.2 : Construction IAQ Management Plan-Before Occupancy

POSSIBLE POINTS: 1

Withdrawn

IEQc4.1 : Low-Emitting Materials-Adhesives and Sealants

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that all adhesive and sealant products used on the inside of the weatherproofing system and applied on-site have been included in the tables and comply with the VOC limits of the referenced standards for this credit.

IEQc4.2 : Low-Emitting Materials-Paints and Coatings**Awarded : 1**

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that all paint and coating products used on the inside of the weatherproofing system and applied on-site have been included in the tables [and comply with the VOC limits of the referenced standards for this credit.

IEQc4.3 : Low-Emitting Materials-Flooring Systems**Awarded : 1**

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that all interior flooring materials meet or exceed applicable criteria for the Carpet and Rug Institute, South Coast Air Quality Management District, the California Department of Health Standard, or FloorScore; the carpet adhesives used have a VOC level of less than 50 g/L; all floor finishes meet the requirements of SCAQMD Rule 1113; and all tile setting adhesives and grout meet SCAQMD Rule 1168.

IEQc4.4 : Low-Emitting Materials-Composite Wood and Agrifiber Products**Withdrawn**

POSSIBLE POINTS: 1

IEQc5 : Indoor Chemical and Pollutant Source Control**Withdrawn**

POSSIBLE POINTS: 1

IEQc6.1 : Controllability of Systems-Lighting**Awarded : 1**

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

DESIGN FINAL REVIEW

The additional documentation demonstrates compliance.

DESIGN PRELIMINARY REVIEW

The LEED Form states that lighting controls are provided for 100% of building occupants and 100% of shared multi-occupant spaces to enable adjustments that meet needs and preferences. However, to demonstrate compliance, the following must be addressed.

TECHNICAL ADVICE

1. It appears that B262 Security Office and B201 Admin may be inappropriately classified as shared multi-occupant spaces. In individual occupant spaces, workers use standard workstations to conduct individual tasks. Examples are private offices and open office areas with multiple workers. Shared multi-occupant spaces include conference rooms, classrooms, and other indoor spaces used as places of congregation. Revise the form and documentation to ensure that spaces are appropriately classified. Spaces must be classified consistently throughout all submittal documentation. Additionally, the IEQ Space Matrix (<http://www.usgbc.org/resources/eq-space-type-matrix>) provides information regarding the classification of individual occupant and shared multi-occupant for most space types encountered within buildings.

IEQc6.2 : Controllability of Systems-Thermal Comfort**Not Attempted**

POSSIBLE POINTS: 1

REVISED REVIEW COMMENT

The LEED Form states that thermal controls are provided for 55.56% of building occupants and 72.73% of shared multi-occupant spaces to enable adjustments that meet needs and preferences. However, to demonstrate compliance, the following must be addressed.

TECHNICAL ADVICE

1. It appears that B262 Security Office and B201 Admin may be inappropriately classified as shared multi-occupant spaces. In individual occupant spaces, workers use standard workstations to conduct individual tasks. Examples are private offices and open office areas with multiple workers. Shared multi-occupant spaces include conference rooms, classrooms, and other indoor spaces used as places of congregation. Revise the form and documentation to ensure that spaces are appropriately classified. Spaces must be classified consistently throughout all submittal documentation. Additionally, the IEQ Space Matrix (<http://www.usgbc.org/resources/eq-space-type-matrix>) provides information regarding the classification of individual occupant and shared multi-occupant for most space types encountered within buildings.

2. The form indicates that thermal controls have been provided for 72.73% of shared multi-occupant spaces; however, the credit requires that 100% of shared multi-occupant spaces are provided with controls. Provide additional information to confirm that all shared multi-occupant spaces have been provided with the required controls.

IEQc7.1 : Thermal Comfort-Design

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1

DESIGN PRELIMINARY REVIEW

The LEED Form states that the mechanically ventilated and mechanically conditioned project space is in compliance with ASHRAE 55-2004.

IEQc7.2 : Thermal Comfort-Verification

POSSIBLE POINTS: 1

Not Attempted

IEQc8.1 : Daylight and Views-Daylight

POSSIBLE POINTS: 1

Withdrawn

IEQc8.2 : Daylight and Views-Views

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project has provided direct line of sight views from 91.26% of all regularly occupied spaces.

Please note, the Supplemental Daylight and Views Calculation Spreadsheet indicates that floors 19 and 20 have no views at seated height, which appears to be a mistake entry in the spreadsheet. Additionally, it appears that spaces without views on the lower floors have been included in the calculation as containing views (Example, 702A Mani/Pedi, 203 Store/Prep) and sight lines have been done incorrectly on the plans. Refer to Figures 3 and 4 within the IEQc8.2 section of the LEED BD+C v2009 Reference Guide. For future projects ensure that any corner areas without lines of sight are accounted for in the calculations. As a result of these issues, it does not appear that the minimum threshold of 90% is affected; however, these issues should be noted for future projects.



Innovation In Design

IDc1.1 : Innovation in Design - Public Transportation

Awarded : 1

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project achieves exemplary performance for SSc4.1: Alternative Transportation - Public Transportation Access. The project location has at least double the transit lines required for the base credit, and the total frequency is 391 rides per day.

IDc1.1 : Innovation in Design

Not Attempted

POSSIBLE POINTS: 1

IDc1.2 : Innovation in Design- SSC5.2 40% Open Space

Awarded : 1

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project achieves exemplary performance for SSc5.2: Site Development - Maximize Open Space. The requirement for exemplary performance for Case 3 is 40% and the project has documented 42.1%.

IDc1.2 : Innovation in Design

Not Attempted

POSSIBLE POINTS: 1

IDc1.3 : Innovation in Design-MRp2 Solid Waste Management Policy

Awarded : 1

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

DESIGN PRELIMINARY REVIEW

The LEED Form states that the project team has developed and implemented an ID credit proposal in compliance with LEED-EBOM 2009 MRp2: Solid Waste Management Policy. The policy has been provided.

IDc1.3 : Innovation in Design

Not Attempted

POSSIBLE POINTS: 1

IDc1.4 : Innovation in Design

Not Attempted

POSSIBLE POINTS: 1

IDc1.4 : Innovation in Design - Green Education

Awarded : 1

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that the project team has developed and implemented a Public Education program. This strategy is detailed in the LEED BD+C v2009 Reference Guide. The documentation provided for the development of a case-study and guided tours complies with the Reference Guide requirements.

IDc1.5 : Innovation in Design

Not Attempted

POSSIBLE POINTS: 1

IDc1.5 : Innovation in Design - MRC5 Regional Material Exemplary Performance

Awarded : 1

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that the project achieves exemplary performance for MRc5: Regional Materials. The requirement for exemplary performance is 30% and the project has documented 63.42%.

IDc2 : LEED® Accredited Professional

POSSIBLE POINTS: 1

ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

Awarded : 1

CONSTRUCTION PRELIMINARY REVIEW

The LEED Form states that a LEED AP has been a participant on the project development team.



Regional priority credits

SSc3 : Brownfield Redevelopment
POSSIBLE POINTS: 1

SSc6.1 : Stormwater Design-Quantity Control
POSSIBLE POINTS: 1

SSc7.1 : Heat Island Effect, Non-Roof
POSSIBLE POINTS: 1

SSc7.2 : Heat Island Effect-Roof
POSSIBLE POINTS: 1
ATTEMPTED: 1, DENIED: 0, PENDING: 0, AWARDED: 1

EAc2 : On-Site Renewable Energy
POSSIBLE POINTS: 1

MRc1.1 : Building Reuse-Maintain Existing Walls, Floors and Roof
POSSIBLE POINTS: 1

TOTAL	110	54	0	0	54
-------	-----	----	---	---	----

REVIEW SUMMARY

Review	POINTS:					
	SUBMITTED	RETURNED	SUBMITTED	DENIED	PENDING	AWARDED

Design Preliminary	04/26/2018	05/23/2018	39	0	12	27
--------------------	------------	------------	----	---	----	----

Credit	STATUS	TYPE	POINTS: ATTEMPTED	DENIED	PENDING	AWARDED
Minimum Program Requirements	Approved		0	0	0	0
Project Summary Details	Approved		0	0	0	0
Occupant and Usage Data	Approved		0	0	0	0
Schedule and Overview Documents	Approved		0	0	0	0
Site Selection	Anticipated	Design	1	0	0	1
Development Density and Community Connectivity	Anticipated	Design	5	0	0	5
Alternative Transportation-Public Transportation Access	Anticipated	Design	6	0	0	6
Alternative Transportation-Bicycle Storage and Changing Rooms	Anticipated	Design	1	0	0	1
Alternative Transportation-Parking Capacity	Anticipated	Design	2	0	0	2
Site Development-Maximize Open Space	Anticipated	Design	1	0	0	1
Heat Island Effect-Roof	Anticipated	Design	2	0	0	2
Water Use Reduction-20% Reduction	Anticipated	Design	0	0	0	0
Water Efficient Landscaping	Pending	Design	2	0	2	0
Water Use Reduction	Anticipated	Design	2	0	0	2
Minimum Energy Performance	Pending	Design	0	0	0	0
Fundamental Refrigerant Management	Anticipated	Design	0	0	0	0
Optimize Energy Performance	Pending	Design	7	0	7	0
Enhanced Refrigerant Management	Anticipated	Design	2	0	0	2
Storage and Collection of Recyclables	Pending	Design	0	0	0	0
Minimum Indoor Air Quality Performance	Anticipated	Design	0	0	0	0
Environmental Tobacco Smoke (ETS) Control	Pending	Design	0	0	0	0
Outdoor Air Delivery Monitoring	Pending	Design	1	0	1	0
Controllability of Systems-Lighting	Pending	Design	1	0	1	0
Thermal Comfort-Design	Anticipated	Design	1	0	0	1
Daylight and Views-Views	Anticipated	Design	1	0	0	1
Innovation in Design - Public Transportation	Anticipated	Design	1	0	0	1
Innovation in Design- SSC5.2 40% Open Space	Anticipated	Design	1	0	0	1
Innovation in Design-MRp2 Solid Waste Management Policy	Anticipated	Design	1	0	0	1

Design Final	02/08/2019	02/26/2019	11	2	0	9
---------------------	-------------------	-------------------	-----------	----------	----------	----------

Credit	STATUS	TYPE	POINTS: ATTEMPTED	DENIED	PENDING	AWARDED
Water Efficient Landscaping	Denied	Design	2	2	0	0
Minimum Energy Performance	Anticipated	Design	0	0	0	0
Optimize Energy Performance	Anticipated	Design	7	0	0	7
Storage and Collection of Recyclables	Anticipated	Design	0	0	0	0
Outdoor Air Delivery Monitoring	Anticipated	Design	1	0	0	1
Controllability of Systems-Lighting	Anticipated	Design	1	0	0	1

Design Appeal	03/14/2019	04/16/2019	2	0	0	2
---------------	------------	------------	---	---	---	---

Credit	STATUS	TYPE	POINTS: ATTEMPTED	DENIED	PENDING	AWARDED
Water Efficient Landscaping	Anticipated	Design	2	0	0	2

Construction Preliminary	05/21/2021	06/07/2021	18	0	5	13
---------------------------------	-------------------	-------------------	-----------	----------	----------	-----------

Credit	STATUS	TYPE	POINTS: ATTEMPTED	DENIED	PENDING	AWARDED
Construction Activity Pollution Prevention	Pending	Construction	0	0	0	0
Fundamental Commissioning of the Building Energy Systems	Pending	Construction	0	0	0	0
Enhanced Commissioning	Pending	Construction	2	0	2	0
Measurement and Verification	Awarded	Construction	1	0	0	1
Construction Waste Management	Awarded	Construction	2	0	0	2
Recycled Content	Awarded	Construction	2	0	0	2
Regional Materials	Awarded	Construction	2	0	0	2
Minimum Indoor Air Quality Performance	Awarded	Design	0	0	0	0
Environmental Tobacco Smoke (ETS) Control	Awarded	Design	0	0	0	0
Construction IAQ Management Plan-During Construction	Pending	Construction	1	0	1	0
Low-Emitting Materials-Adhesives and Sealants	Awarded	Construction	1	0	0	1
Low-Emitting Materials-Paints and Coatings	Awarded	Construction	1	0	0	1
Low-Emitting Materials-Flooring Systems	Awarded	Construction	1	0	0	1
Innovation in Design - Green Education	Awarded	Construction	1	0	0	1
Innovation in Design - MRC5 Regional Material Exemplary Performance	Awarded	Construction	1	0	0	1
LEED® Accredited Professional	Awarded	Construction	1	0	0	1
	Pending		2	0	2	0

Construction Final	06/16/2021	06/22/2021	3	0	0	3
--------------------	------------	------------	---	---	---	---

Credit	STATUS	TYPE	POINTS: ATTEMPTED	DENIED	PENDING	AWARDED
Construction Activity Pollution Prevention	Awarded	Construction	0	0	0	0
Fundamental Commissioning of the Building Energy Systems	Awarded	Construction	0	0	0	0
Enhanced Commissioning	Awarded	Construction	2	0	0	2
Construction IAQ Management Plan-During Construction	Awarded	Construction	1	0	0	1